



PURCHASING SECTION
13450 – 104 Avenue, Surrey BC V3T 1V8
Tel: 604-590-7274
E-mail: purchasing@surrey.ca

ADDENDUM NO. 1

REQUEST FOR QUOTATIONS (RFQ) NO.: 1220-040-2019-081
TITLE: BEAR CREEK WALKING TRACK
RUBBER SURFACE
ADDENDUM ISSUE DATE: September 20, 2019
CLOSING DATE AND TIME: PREFER TO RECEIVE QUOTATIONS ON
OR BEFORE OCTOBER 1, 2019.

INFORMATION FOR CONTRACTORS

This Addendum is issued to provide additional information to the RFQ for the above named project, to the extent referenced and shall become a part thereof. No consideration will be allowed for extras due to the Contractor not being familiar with this Addendum. This Addendum No. 1 contains two (2) pages.

FOR INFORMATION ONLY:

- Due to project timeline, no questions may be entertained which are received less than five business days prior to closing.

QUESTIONS & ANSWERS:

Q1: Is the city self performing all the prep work, plumbing, excavation, grading and so on? The scope that requires pricing would be the supply and install of the new rubber track and painting only

A1: Yes, the City will be self-performing all other works, including excavation, grading, drainage, and base preparation. This RFQ asks for pricing for the supply and installation of the rubber surface, which the painting is considered incidental to.

Q2: Schedule B – Appendix 2 Supplementary Specifications. Part 1 – 1.1.2 Pour a mock up at the location and size as identified on the drawings.
a. We have reviewed drawings and do not see where this is to be installed. Please clarify.
b. Please indicate, location, size and colour.
c. When does the city want this installed?
d. Will all proponents be required to install this as party of qualifications for the RFQ?

A2: There is no specific location requirement for the mock up

- a. The mockup will be a 3m long section of the final track (3m x 5.1m) surface in the proposed colour. The Contract Administrator will review and approve before pouring of the rest of the wear/surface mat.
- b. The mock up should be prepared prior to the installation of the wear/surface mat.
- c. Only the selected proponent will be required to prepare a mock up during the construction process

Q3: Temporary Fencing – Will the city be erecting temporary 6’ high fencing around the entire perimeter of the walking path? If so will this remain up until the completion of the rubber surface portion?

A3: City of Surrey will be erecting construction fencing around the entire perimeter of the walking path for the purposes of restricting public access to the construction zone. The fencing will remain in place during the period of rubber installation. The City will not guarantee site security. Contractor is fully responsible for their materials and installation until such time as their scope of work has achieved substantial completion and accepted by the City.

Q4: Completion date of November 8th – Is there a significance behind this completion date?

A4: The completion date is based on the likely availability of weather suitable for the installation of the rubber surface.

END OF ADDENDUM

All Addenda will become part of the RFQ Documents.
