



**PURCHASING SECTION**  
13450 – 104 Avenue, Surrey, BC V3T 1V8  
Tel: 604-590-7274  
E-mail: [purchasing@surrey.ca](mailto:purchasing@surrey.ca)

**ADDENDUM No. 4**

---

**INVITATION TO TENDER No.:** 1220-020-2019-004

**TITLE:** ANNIEDALE SCHOOL AND SURREY  
TOWN HALL REHABILITATION

**ADDENDUM ISSUE DATE:** JUNE 4, 2019

**CLOSING DATE AND TIME:** ON OR BEFORE THE FOLLOWING DATE AND  
TIME (THE "CLOSING TIME"):

**TIME:** 11:00 A.M. (LOCAL TIME)

**DATE:** JUNE 6, 2019

---

**INFORMATION FOR TENDERERS**

This Addendum is issued to provide additional information and clarifications to the ITT for the above named project, to the extent referenced and shall become a part thereof. No consideration will be allowed for extras due to the Tenderer not being familiar with this addendum. This Addendum No. 4 contains one (1) page and an attachment, two (2) pages in total.

**CLARIFICATION:**

**1.0** Refer to the attached **Electrical Addendum 02** for electrical clarifications.

**- END OF ADDENDUM -**

---

**All Addenda will become part of the Contract Documents.**

---



## Electrical Addendum No. 02

PROJECT NAME:	Anniedale School & 1881 Surrey Town Hall Rehabilitation	PROJECT NO:	2-18-159/160
ARCHITECT/PRIME CONSULTANT:	McGinn Engineering & Preservation Ltd.	DATE:	June 4, 2019
		PAGE:	1 of 1
DOCUMENT12			

THE FOLLOWING ADDENDUM SUPERCEDES INFORMATION CONTAINED IN DRAWINGS AND SPECIFICATIONS ISSUED FOR THE PROJECT TO THE EXTENT REFERENCED. THIS ADDENDUM FORMS PART OF THE TENDER DOCUMENTS AND IS SUBJECT TO ALL OF THE CONDITIONS SET OUT IN THE CONTRACT CONDITIONS.

### 1. RFI

#### 1.1 What is the distance from the Museum Electrical Room to each of the new Buildings? Given that the surfaces must be hooked up to the Museum Building.

- .1 ANNIEDALE SCHOOL IS APPROXIMATELY 28M FROM THE ELECTRICAL ROOM IN THE NORTH WING OF THE MUSEUM. THE 1881 HALL IS APPROXIMATELY 45M FROM THE ELECTRICAL ROOM IN THE NORTH WING OF THE MUSEUM.

#### 2.1 How is the Data/Tel/Security and Fire Alarm getting to the buildings, and where is it fed from? Overhead, underground etc.

- .1 DATA/TEL/SECURITY AND FIRE ALARM OF EACH BUILDING ARE TO BE FED FROM ONE (1) EXISTING 2" C STUB-UP FROM THE MUSEUM. THE CONDUITS ARE UNDERGROUND.

#### 3.1 The Electrical Drawings say to re-use the existing 2" Conduit but where is the existing located? Both Buildings aren't shown to have existing panels.

- .1 THE EXISTING 2" C ARE CONNECTING BETWEEN THE PROPOSED LOCATIONS OF THE TWO HERITAGLE BUILDINGS AND THE ELECTRICAL ROOM IN THE NORTH WING OF THE MUSEUM.

#### 4.1 What is the specification on the existing light that just get the Shades Replaced? [This refers to the DELETE new Anniedale pendant light fixtures and replace the existing glass shades only with...on the Tender Doc]

- .1 ALL LIGHTINGS ARE GOING TO BE NEW. ALL EXISTING LIGHTING ARE TO BE REMOVED BACK TO SOURCE.

END OF ELECTRICAL ADDENDUM NO. 02