



## PROCUREMENT SERVICES

CITY OF SURREY, SURREY CITY HALL  
13450 – 104 Avenue, Surrey, B.C., V3T 1V8  
Tel: 604-590-7274  
E-mail: [purchasing@surrey.ca](mailto:purchasing@surrey.ca)

### ADDENDUM No. 2

---

REQUEST FOR QUOTATION No.: 1220-040-2022-077

TITLE: GUILDFORD LIBRARY: AIR HANDLING UNITS  
REPLACEMENTS

ADDENDUM ISSUE DATE: OCTOBER 7, 2022

**REVISED DATE: PREFER TO RECEIVE SUBMISSION ON OR  
BEFORE OCTOBER 12, 2022**

---

### INFORMATION FOR CONTRACTORS

Contractors are advised that Addendum No. 2 to 1220-040-2022-077 is hereby issued by the City. This addendum shall form part of the contract documents and is to be read, interpreted and coordinated with all other parts. The following information is provided to answer questions raised by Contractors for the above-named project, to the extent referenced and shall become a part thereof. No consideration will be allowed for extras due to the Contractors or any sub-contractor not being familiar with this addendum. This Addendum No. 2 contains 2 (two) pages.

#### QUESTIONS AND ANSWERS:

**Q1. Please confirm that the proposed AHU will fit with the existing duct connections and roof penetrations.**

**A1. It is the Contractor's responsibility to measure all site conditions and confirm all dimensions before proceeding with shop drawings.**

**Q2. Please confirm no duct cleaning required.**

**A2. Duct cleaning will not be required.**

**Q3. Please specify base Electrical contractor on the job.**

**A3. Prime Contractor to select qualified Electrical Contractor for the job.**

**Q4. Please confirm aluminum jacketing requirement on refrigerant piping, condensate lines.**

**A4. Aluminum jacketing on insulation of refrigerant lines to protect insulation from damage from birds.**

**Q5. Please specify the model number, dimensions, tonnage of existing AHU?**

**A5. See M2.01 for curb dimensions.**

**AHU-1**

**Model: FWB-403/DJE-100-MO**

**Dimensions: 317"x 118"x 93"**

**Tonnage: 20.83 tons**

**AHU-3**

**Model: FWA-92/DJ-20-0**

**Dimensions: 167"x62"x40"**

**Tonnage: 16.6 tons**

**AHU-6**

**Model: FWA-133/DJE-40-MO**

**Dimensions: 260" X 75" X 61"**

**Tonnage: 20.83 tons**

**Q6. Please confirm size of the gas line to the existing and new AHUs. Also, it looks like there is rust on the gas pipe, do we need to allow for painting.?**

**A6. Size of gas line to the existing and new AHUs:**

**AHU-1 – 1¼" line**

**AHU-3 – 1" line**

**AHU-6 – ¾" line**

**Painting existing gas lines not required.**

---

**All Addenda will become part of the Contract Documents.**

---

**- END OF ADDENDUM -**